

## CONSTRUCTION PRODUCTS TESTING LABORATORY

Reģ. Nr. 40003010053

Kr.Barona str. 99, Riga, LV 1012, telephone/ fax 67291625, 29239237, tursons.lab@gmail.com Regulation (EU) No 305/2011-Construction produkts

## TEST REPORT No. 15/971-1a

Date: 10.09.2015.

Customer: LLC "PRE "UKRMAGNESIT".

Order: 17.08.2015.

Information of testing samples:

Date of samples delivery	Date of testing	Testing object	Customer samples No. (code)	ID of samples for laboratory
17.08.2015.	17.08.2015 02.09.2015.	Magnesite board	Standard Premium	15/6241-15/6245 15/6253-15/6257

Obtaining the samples is the responsibility of the customer.

Customer information: Magnesite board.

**Information of samples:** Size of samples 500x400x10mm (10 samples), samples without defects.

Test carried out according to LVS EN 12467:2013 requirements. Condition of testing: air temperature +22°C, relative air humidity 56%.

Equipment used for testing: Square, Scale, metal rule, smooth.

## Test results.

## 1. Determination of water absorption and deviation from flatness for magnesite board samples.

	ID of	Customer	Deviation from flatness,	Water	Thickness
	samples	samples	mm	absorption,	swelling, %
	for	No.(code)		%	
	laboratory				# 11 A B
	15/6241	*	Thickness deviation 0.01mm	20.1	No changes
	15/6242	Standard	Length deviation 0.03mm	22.9	in thickness
1	15/6243			20.1	
	15/6244			21.2	2 2
	15/6245		w.,~	20.2	
	Average		ā.	20.9	r
	15/6253	Premium	Thickness deviation 0.01mm	14.8	No changes
	15/6254		Length deviation 0.03mm	14.3	in thickness
0	15/6255			14.1	88.8
İ	15/6256			14.9	
	15/6257			15.0	a .
o)	Average			14.6	

This test report contains experimental results from the BTL testing record No 15.761.

The test results are valid only for this tested samples batch.

All test report and it's parties can't be reprinted without laboratory written consent.

Head of testing laboratory/ Testing performed by Mg.sc.ing.,S.Siļutina O.Ivanova

dymateriālu estēšanas

laboratorija

ratorija 🔊

BTL V17/01.2015

Test report No.15/971-1a

1(1)